PLATFORM SUPPLY VESSELS (PSV / MPSV)

DP2 Platform Supply Vessel — Methanol Capability

DP2 · FiFi-1	688 m² deck	Methanol transport	32 POB

SCOPE OF WORK

A DP2, FiFi-1 platform supply vessel built for deep-water operations, with a 688 m² deck (51 x 13.5 m) and dedicated methanol transport capacity alongside standard liquid mud, fuel and dry bulk/cement handling. A moon pool is fitted for ROV operations, and accommodation is provided for 32 persons.

Principal Particulars

Type	DP2, FiFi-1 platform supply vessel
Gross / net tonnage	2,641 / 648
Deck area	51.00 m x 13.50 m (688 m²)

Machinery & Propulsion

Propellers	2 x CPP
Bow / stern thruster	590 kW tunnel each
Forward azimuth thruster	590 kW
Shaft generators	2 x 1,800 kVA

Capacities & Rates

Base oil delivery	200 m³/h @ 9 bar
Dry bulk/cement	2 x 22.7 m³/h @ 5.6 bar
Service / economic speed & consumption	16 m³/day @ 12 kn / 9 m³/day @ 10 kn

Deck Equipment	
Tuggers / capstans	2 x 10 t / 2 x 8 t
Provisions crane	3 t @ 16 m
Firefighting (FiFi-1)	2 x 1,600 m³/h pumps, 2 x 1,200 m³/h monitors
DP	Class DP2, 1 moon pool prepared for HiPAP

Accommodation & Comms	
Total capacity	32 persons
Navigation	2 radar, 3 gyro, echo sounder, autopilot, 2 DGPS
Comms	GMDSS A3, 2 Inmarsat C, FleetBroadband, VSAT